GOVERNMENT OF ANDHRA PRADESH

ABSTRACT

R&B Deptt- Widening and Strengthening of Ongole- Nandyal road from Km 1/5 to 9/0 in Prakasam District - Corenet Plan– Administrative Sanction-Accorded – Orders – Issued.

TRANSPORT, ROADS & BUILDINGS (R.IV) DEPARTMENT

G.O.Rt.No.606 Dated:28.10.2016

Read:

From the CE (R&B) CRN & MD, APRDC, AP., Lr No: 299 /Plnwrks/ GM/DCE-I/DEE-5/AEE-14/CRN/Ongl/Repns/2014, Dt:05.08.2016.

***

ORDER:

In the letter read above, the Chief Engineer (R&B) CRN &MD, APRDC, has stated that the Ongole –Nandyal road is an important State Highway passing through the famous pilgrimage place Srisailam. The road at Km.1/2 joins NH-16. The stretch of the road from Km. 0/0 to 1/5 is CC Pavement with multilane and the remaining length is 7.00m width with BT carriageway. The proposed stretch of Km. 1/5 to 9/0 of Ongole-Nandyal road passes through Municipal Corporation limits with heavy built up area. If it is upgraded as NH, the NH road will not run in the Municipal limits, at Km. 9/0, a bypass will be formed to join NH-16 to avoid traffic congestion in the Ongole urban limits. It has 5 black spots in 5Km length stretch due to number of business and residential colonies. Ramatheertham village located at Km. 24/0 to 28/0 of Ongole-Nandyal road is famous throughout the world for export variety of "Galaxy Granite" mineral which is being transported in huge blocks on multi-axle vehicle to Chennai port through this road.

2. He has also stated that the road from Km. 0/0 to 9/0 lies in Ongole urban limits. In addition to the usual normal domestic traffic, multi axle vehicles and heavy vehicles carrying granite blocks and construction material ply on this road stretch. The existing 7.0m BT carriageway is unable to cater to the needs of this traffic. Hence 4-laning on this road is very much essential on this stretch. In view of the above, he has proposed to widen the existing double lane road to 4-lane from Km. 1/5 to 9/0 in the built up area of Municipal Corporation limits of Ongole. Further, CC pavement in the busy stretch of Km. 1/5 to 3/0 with drains and hard shoulders for 1.50m width are proposed on either side of the carriageway for easy negotiation of vehicles and to avoid formation of low berms.No land acquisition is required for 4-laning of this road. However utilities are to be shifted while executing the work for which requisitions were already submitted to the concerned authorities for taking necessary action. An amount of Rs. 1,00,00,000/- is required towards Shifting of Utilities and the same is provided as lumpsum in the estimate. The traffic Intensity on this road is very high about 7452 CVPDs and 31681 PCUs/day, thus qualify for four lane as IRC Specification.

(PTO)

3. The Chief Engineer (R&B) CRN & MD, APRDC, AP, has requested to accord administrative sanction for an amount of Rs. 25.00 Crores; for the work of "Widening and Strengthening of Ongole- Nandyal road from Km 1/5 to 9/0 in Prakasam District", under Coronet Plan.

4. After careful examination of the matter, Government decide and hereby accord Administrative for an amount of Rs. 25.00 Crores; for the work of "Widening and Strengthening of Ongole- Nandyal road from Km 1/5 to 9/0 in Prakasam District, under Corenet Plan, Subject to condition that cost of shifting of utilities will have to be borne by the concerned urban local body.

5. The amount sanctioned in Para (4) above, shall be met from the Head of account -5054–Capital outlay on Roads & Bridges-04 -District & other Roads-MH800- Other Expenditure-GH 11-SDP- SH(33)–Core net Works Roads (works)-530–Major works-531–OE.

6. The Chief Engineer (R&B) CRN & MD, APRDC, AP., shall take further action in the matter accordingly.

7. This orders issues with the concurrence of Finance Department vide their U.O.No. 17023/409/FMU-TR&B/2016., Dt: 24.08.2016.

(BY ORDER AND IN THE NAME OF THE GOVERNOR OF ANDHRA PRADESH)

B.SAM BOB
SPECIAL CHIEF SECRETARY TO GOVERNMENT

To
The Chief Engineer (R&B) CRN & MD, APRDC, AP., Amaravati

Copy to:

The Pay and Accounts Officer, AP., Amaravati
The Director of Works and Accounts, A.P., Amaravati
The District Treasury Officer, Prakasam District at Ongole
The PS to Spl. C.S, TR&B/ M(TR&B)
The Finance (FMU.TR&B) Deptt.
Sf/Sc.

//FORWARDED BY ORDER//

SECTION OFFICER